

George C. Marshall Space Flight Center
Marshall Space Flight Center, Alabama 35812

ED27-CDL-SOP-001 Baseline August 2, 1999

STANDARD OPERATING PROCEDURE

ED27 / STRUCTURAL AND DYNAMICS TEST GROUP

CONTROL DYNAMICS LABORATORY

CHECK THE MASTER LIST—
VERIFY THAT THIS IS THE CORRECT VERSION BEFORE USE

Marshall Space Flight Center Standard Operating Procedure			
ED27/Structural and Dynamics Test Group			
Control Dynamics Laboratory ED27-CDL-SOP-001 Revision: Baseline			
	Date: August 2, 1999	Page 1 of 7	

DOCUMENT HISTORY LOG

Status (Baseline/ Revision/ Canceled)	Document Revision	Effective Date	Description
		2-24-98	Document number ED73-CDL-SOP-001
Baseline			
Baseline	Draft 1	8-2-99	Updated document numbers from reorganization and integrated document system.

Marshall Space Flight Center Standard Operating Procedure		
ED27/Structural and Dynamics Test Group		
Control Dynamics Laboratory ED27-CDL-SOP-001 Revision: Baseline		
	Date: August 2, 1999	Page 2 of 7

STANDARD OPERATING PROCEDURE FOR THE CONTROL DYNAMICS LABORATORY

1. SCOPE

- 1.1 <u>Scope</u>. This standard operating procedure (SOP) provides instructions for the general operating procedures of performing tests and experiments in the Control Dynamics Laboratory (CDL) at Marshall Space Flight Center.
- 1.2 <u>Purpose</u>. The CDL is used to implement, test, and verify control methods for all types of mechanical and mechanical /optical systems. The CDL characterizes and modifies the structural dynamic behavior of these systems through system identification and control, structure interaction methods and techniques.
- 1.3 Applicability. This work instruction applies to all personnel in the CDL.
- 1.4 System Description. Definitions in MPG-1410.1, ED27-OWI-001, ED27-OWI-002, and ED27-OWI-003 apply.
- 1.5 <u>General</u>. The test engineer of the CDL shall be responsible for coordination and enforcement of the document activities.

2. APPLICABLE DOCUMENTS

MPG 8730.5	Control of Inspection, Measuring, and Test Equipment
ED27-OWI-M&V-001	Document Control
ED27-OWI-M&V-002	Quality Records Control
ED27-OWI-M&V-003	Test Report Control
ED27-CDL-FOP-001	Use of Ometron Laser Vibrometer for Dynamic Testing
ED27-EMA-FOP-001	Mounting of PCB Tri-Axial Adapter for Modal Surveys

Marshall Space Flight Center Standard Operating Procedure			
ED27/Structural and Dynamics Test Group			
Control Dynamics Laboratory ED27-CDL-SOP-001 Revision: Baseline			
	Date: August 2, 1999	Page 3 of 7	

2. APPLICABLE DOCUMENTS (continued)

ED27-EMA-FOP-002	PCB Multichannel Acclerometer System Setup and Calibration for Modal Surveys
ED27-EMA-FOP-006	Air Bag Functional Test for Modal Surveys
ED27-EMA-FOP-007	Bungee Functional Test for Modal Surveys
ED27-EMA-FOP-009	Calibration of PCB 333A, 333B Accelerometers for Modal Testing
ED27-EMA-FOP-013	ICP Accelerometer Calibration for Modal Surveys

3. REFERENCE DOCUMENTS

Associated Equipment Manuals

SSC Facility Operator's Manual

Operator's Manual for the CSI/CASES GTF

Filter Control Unit User's Manual MN-33B

Operating Instructions for 900 Watt PWM Servo Amplifier with Current Loop Configuration for Brushless DC Motors BLM1-07012CBXX

BDS5 Goldline™ Positioner User's Manual BDS5-MAN-2.0.4

Marshall Space Flight Center Standard Operating Procedure			
ED27/Structural and Dynamics Test Group			
Control Dynamics Laboratory ED27-CDL-SOP-001 Revision: Baseline			
	Date: August 2, 1999	Page 4 of 7	

4. SAFETY

All set-up and operating procedures mentioned under user manuals BLM1-07012CBXX and MN-33B shall be followed in order to minimize the risk of injury due to electric shock when using the filter control unit and the 900 watt PWM servo amplifier for the brushless DC motor. Likewise, when using the BDS5 Goldline positioner, all mounting and wiring procedures shall be implemented as specified in document BDS5-MAN-2.0.4.

Use of the ground test facilities, ACES and CASES, shall conform with the appropriate operators manuals to ensure safe system level performance.

When using any laser equipment, care shall be taken in order to prevent the laser from being operated in or around any flammable or combustible material and that controls are in place to prevent exposure of the laser into eyes of test personnel or passersby.

5. ACTIVATION PREPARATIONS

- 5.1 All appropriate and pertinent documents regarding the operation and procedure of various elements of the CDL shall be followed.
- 5.2 The Test Engineer shall use appropriate procedures as necessary and/or specified to provide a consistent, reliable monitoring, simulation, test, and/or data acquisition of test articles in the CDL.
- 5.3 The Test Engineer shall select appropriate instrumentation to measure the dynamic response of a test article. Any calibration and mounting procedures shall be conducted as specified by the above applicable documents.
- 5.4 Before using test equipment, the Test Engineer shall verify that the equipment has been properly calibrated and the calibration date has not expired. Equipment calibration and servicing shall conform to MPG 8730.5, in addition to pertinent service manuals.

Marshall Space Flight Center Standard Operating Procedure			
ED27/Structural and Dynamics Test Group			
Control Dynamics Laboratory ED27-CDL-SOP-001 Revision: Baseline			
	Date: August 2, 1999	Page 5 of 7	

6. PROCEDURE

- 6.1 Set up and configure the necessary test equipment and software for the test. Validate and characterize proper operation following the procedures given in the above listed documents.
- 6.2 Install the test article in or on its appropriate test fixture. Mount any necessary instrumentation to the test article. When performing modal tests the following applicable FOPs shall be followed if the associated equipment is used:

ED27-EMA-FOP-001, ED27-EMA-FOP-002, ED27-EMA-FOP-006, ED27-EMA-FOP-007, ED27-EMA-FOP-009, ED27-EMA-FOP-013

- 6.3 Follow the appropriate procedures given in the above applicable documents regarding equipment and/or facility operation. Tests using the ACES or CASES ground test facilities shall follow the procedure given in SSC Facility Operator's Manual or the Operator's Manual for the CSI/CASES GTF. Tests performed using the Ometron® VPI Sensor shall conform to the procedures set forth in ED27-CDL-FOP-001. The test engineer shall determine which instrument(s) are most appropriate to use.
- 6.4 Data acquisition shall conform to the appropriate test plan. The test shall be performed until the test engineer determines that an appropriate amount of data is properly collected.

7. POST TEST VERIFICATION

The last page of a TCP will be a "Post Test Verification Sheet". TCPs covering testing of certification test articles will use the sheet with a Quality Monitor sign-off. See Appendix A for the form.

Marshall Space Flight Center Standard Operating Procedure			
ED27/Structural and Dynamics Test Group			
Control Dynamics Laboratory ED27-CDL-SOP-001 Revision: Baseline			
	Date: August 2, 1999	Page 6 of 7	

APPENDIX A

Marshall Space Flight Center Standard Operating Procedure			
ED27/Structural and Dynamics Test Group			
Control Dynamics Laboratory ED27-CDL-SOP-001 Revision: Baseline			
	Date: August 2, 1999	Page 7 of 7	

POST-TEST VERIFICATION

The Test and Checkout Proceduresatisfactorily completed and documented.		has been
Test Engineer	Date	
Quality Monitor	Date	_